

ARTIST'S IMPRESSION OF THE PROPOSED IMPROVEMENTS ON RINGWOOD ROAD LOOKING SOUTH TOWARDS NEWTOWN BUSINESS PARK

EXISTING FOOTWAY ON WESTERN SIDE OF RINGWOOD ROAD TO BE UPGRADED TO SHARED FOOTPATH FOR BOTH WALKING AND CYCLING

EXISTING CROSSING POINT TO BE UPGRADED TO TOUCAN CROSSING

BUS LAYBY TO BE REMOVED AND SHELTER UPGRADED

DEDICATED RIGHT-TURN FILTER LANE ON RINGWOOD ROAD TO BE REMOVED. VEHICLES WILL STILL BE ABLE TO TURN RIGHT INTO ALBION CLOSE

ROUTE CONTINUES TOWARDS POOLE TOWN CENTRE

PUFFIN CROSSING TO BE REMOVED AND NEW BUS STOP TO BE INSTALLED WITH NEW SHELTER

BUS LAYBY TO BE REMOVED AND NEW TOUCAN CROSSING POINT TO BE INSTALLED

REFUGE TO BE REMOVED AND JUNCTION RADIUS TO BE TIGHTENED

BUS LAYBY TO BE REMOVED AND SHELTER UPGRADED

NEW NORTHBOUND BUS LANE TO BE INSTALLED ON WESTERN SIDE OF RINGWOOD ROAD FROM CRANBROOK ROAD TO OLD WAREHAM ROAD ROUNDABOUT. ACCESS TO/FROM PROPERTIES WILL BE MAINTAINED

ZEBRA CROSSING POINT TO BE REMOVED

SOME TREES ALONG RINGWOOD ROAD TO BE REMOVED. NEW TREES TO BE PLANTED IN SIMILAR LOCATIONS. ADDITIONAL TREE PLANTING TO BE UNDERTAKEN TO IMPROVE GREEN SPACES

EXISTING UNCONTROLLED CROSSING POINTS UPGRADED TO A TOUCAN CROSSING

OLD WAREHAM ROAD ROUNDABOUT

EXISTING UNCONTROLLED CROSSING POINT LOCATION UNCHANGED

SLIGHT ROUNDABOUT GEOMETRIC REALIGNMENT IMPROVEMENT TO WIDEN FOOTWAY AREA FOR A NEW SHARED USE PATH LINKING THE CROSSING POINTS. GREENSPACE AND LANDSCAPING IMPROVEMENTS.

BUS LAYBY TO BE REMOVED AND SHELTER UPGRADED

DEDICATED RIGHT-TURN FILTER LANE ON RINGWOOD ROAD TO BE REMOVED BUT THE NORTHBOUND LANE WILL BE WIDENED TO ACCOMMODATE VEHICLES TURNING RIGHT INTO ROSSMORE ROAD

EXISTING REFUGE TO BE UPGRADED TO TOUCAN

EXISTING REMOVED TO FACILITATE NEW BUS LANE AND CYCLE TRACK

NEW SOUTHBOUND BUS LANE TO BE INSTALLED ON EASTERN SIDE OF RINGWOOD ROAD BETWEEN MANNINGS HEATH AND OLD WAREHAM ROAD ROUNDABOUT. ACCESS TO/FROM PROPERTIES WILL BE MAINTAINED

BUS LAYBY TO BE REMOVED AND SHELTER TO BE UPGRADED

EXISTING CROSSING POINTS TO BE UPGRADED TO TOUCAN CROSSINGS

ROUTE CONTINUES TO MOUNTBATTEN ROUNDABOUT

EXISTING CROSSING POINT NEAR MANOR AVE IS TO BE RELOCATED TOWARD RINGWOOD ROAD

© Crown copyright and database rights 2022 OS 100019460
© Bluesky International Ltd and Geomapping Plc 2022

KEY:

- CARRIAGEWAY
- FOOTWAY
- CYCLE TRACK
- SHARED PATH
- CONCRETE SEPARATOR
- VERGE
- RED TACTILE PAVING
- BUFF TACTILE PAVING
- KERBLAIE
- WHITE ROAD MARKING
- YELLOW ROAD MARKING
- BUS SHELTER

Rev	Date	Description

Engineering

BCP

Funded by UK Government

Project Title: Transforming Cities Fund SS

Drawing Title: General Arrangement Ringwood Road - SS.3 Sea View Junction to Mannings Heath

Drawn	Checked	Approved
DS	MR	CM

Date	Scales
Jul 24	1:500 @ A1 Ribbon

Drawing Number: 25823_BCP_SS_3_DR_D_100 Rev -

C:\Users\ADRIAN\Desktop\ - WSP C:\Bluesky\temp\Plugin\BCP Documents\Ali Motion - Public